



NOTES:

1. ALL FENCING AND FASTENERS TO BE GALVANIZED PRIOR TO FABRICATION.
2. EXTRUDED BLACK VINYL COATING MAY BE APPLIED PROVIDED ALL FENCING MATERIALS ARE GALVANIZED PRIOR TO COATING. WHERE VINYL COATING APPLIED, ALL FENCING ELEMENTS TO BE COATED.
3. MID-BRACING RAILS REQUIRED WHERE FENCE HEIGHT IS GREATER THAN THAT SHOWN ON THE DETAIL. MID-BRACE TO BE 43mm Ø RAIL ON TERMINAL, CORNER, STRAINING OR GATE POSTS.
4. WIRE MESH SHALL BE MEASURED AT 9 GAUGE *PRIOR* TO GALVANIZING AND/OR ADDITIONAL COATING.
5. CONCRETE FOOTINGS TO BE 20mpa STRENGTH AT 28 DAYS
6. ALL PIPE TO BE SCHEDULE 40.
7. WIRE MESH SHALL BE INSTALLED ON THE CITY PROPERTY SIDE OF FENCE.

CHAINLINK FENCE
WALKWAY BLOCK

The Corporation Of The
**CITY OF
KITCHENER**



			Scale:	N.T.S.
1	MANUAL UPDATE	APR 2015	Date:	MARCH 2012
No.	REVISION	DATE	Std. No.:	507